BRUHAT BANGALORE MAHANAGARA PALIKE

3BMP/2019-20/OW/WORK_INDENT35734/CALL-

APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/09/2019-20, Date: 04.07.2019

Improvements to drains of byatarayanapura gramatana road (road next to HDFC bank) of Byatarayanapura

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of B Girish ( )	
				In Figures	In Words
1	302.74	Earthwork excavation by manual means in rodinary soil involving an average horizontal throw upto 2 m and an average lift upto 1.5m, excavated surafce levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking clods complete as per specifications.	Cum	137.0	Rupees One Hundred Thirty Seven Only
2	41.33	Providing and laying in position plain cement concrete of nominal mix 1:4:8 with OPC @ 180kgs, with 40mm and down size graded granite metal machine mixed, conrete laid in layers not exceeding 15 cms. Thick well compacted in foundation and plinth, including cost of all materials labour, HOM of machinery, curing complete as per specification .	Cum	5408.0	Rupees Five Thousand Four Hundred Eight Only
3	93.53	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320 Kgs with 20mm and down size graded granite metal coarse aggregates @ 0.69 cum and fine aggregates @ 0.460 cum with superplastizers @ 3lts confirming to IS 9103-1999 RE affirmed - 2008 machine mixed, concrete laid in layers not exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, stair case lintels, retaining walls return walls, walls(anythickness) including attached plasters columns piers abutments pillars posts struts butresses string or lacing courses parapets copings, bed blocks , plain windows cills fillets etc., including cost of all materials labour HOM of machinery curing complete as per specifications. Seocifications No. KBS 4.1,4.6	Cum	5998.0	Rupees Five Thousand Nine Hundred Ninety Eight Only
4	5.14	Providing TMT Steel Reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications	Sqm	75223.0	Rupees Seventy Five Thousand Two Hundred Twenty Three Only
5	696	Providing and removing Centering, shuttering, strutting, propping etc., for columns, pillars, piers, abutments, post and struts, square / rectangular slabs /side walls polygon in plan including cost of materials, labour complete as per specification and directions of the Engineer in charge	Sqm	483.0	Rupees Four Hundred Eighty Three Only
6	218.7	Providing and fixing 10cms thick pre cast RCC covering slab using reinforced cement concrete M20 mix with stone aggregate 20mm and down size including centring shuttering reinforcement and bar bending machine mixed concrette laid in layers not exceeding 15 cm thick wellcompacted cost of all materials labour curing complete as per specfications (Data Rate Approved)	Sqm	2100.0	Rupees Two Thousand One Hundred Only
7	265	Providing and fixing Pre cast solid concrete kerb stones made out of CC 1:2:4 of size 450x200x400 mm and finished with CM 1:3 plastering and finishing cutting etc., complete	nos	477.0	Rupees Four Hundred Seventy Seven Only
8	119.25	Providing and applying ready mix priming coat over ocncrete / masonry, / asbestos cement sheet / plastered surfaces includding preparing the surface after thorougly cleaning of oil, grease, dirt and other foreign matter and sand papering including cost of materials, labour compelte as per specifications.	Sqm	39.0	Rupees Thirty Nine Only
9	9	Laying Reinforced cement concrete pipe NP2 / prestressed concrete pipe for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling, concrete and masonry works in head walls and parapets complete as per specifications. MORTH Specification No. 2900 B. 1200 mm dia MORTH Specification No. 1000,2300	m	5976.0	Rupees Five Thousand Nine Hundred Seventy Six Only
10	1.02	Providing 100mm and down size nominal size	cum	987.0	Rupees Nine Hundred Eighty Seven Only
11	0.68	Providing 40mm and down size nominal size	cum	1091.0	Rupees One Thousand Ninety One Only

Signature of the contractor

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of B Girish ( )	
				In Figures	In Words
12	0.68	Providing 20mm and down size nominal size	cum	1091.0	Rupees One Thousand Ninety One Only
13	0.51	Providing Fine aggrgate 2.36mm nominal size	cum	1054.0	Rupees One Thousand Fifty Four Only
14	70	Providing and fixing MS Grating 260x260 mm	nos	84.0	Rupees Eighty Four Only
15	302.74	Loading and unloading of stone boulder/stone aggregates/ sand/ kanker/ moorum. KSRRB M100-1:Placing tipper at loading point loading with front end loading, dumping turning for return trip, excluding time for haulage and return trip complete as per specification MORTH Chapter 1	cum	93.0	Rupees Ninety Three Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92